

Addendum 1

Questions and Answers:

1. The SCOPE states KEYS will provide poles and material. The MATERIALS section states the contractor is responsible for furnishing all line materials except transformers and streetlights. Please clarify what the contractor is actually providing.

The contractor is required to supply all line materials, poles, insulators, cutouts, connectors, etc. to complete project.

In the event of any conflicts between this document and the Bid, these Clarifications shall control.

Amendment of Scope Section:

The project is for replacement of approximately 423 distribution poles throughout KEYS' 13.8 KV system. The contractor is responsible for furnishing all line materials required for the completion of this project with the exception of transformers and streetlights where applicable ~~KEYS will provide poles and distribution line material~~. Details on locations and project requirements are within the attached documents. Work to occur in 2022 and early 2023. KEYS will allow 2-4 crews to work on this project at one time. KEYS poles are designed to meet extreme wind loading as specified in the NESC. As such the poles are to be embedded at 7 feet + 10% of pole height. Pole holes are to be back filled with crushed rock. Refer to drawing M-1447 for installation requirements.

2. There was no photos of the poles in the folder.

We have updated the shared folder to include the photos in Document 2. Please use the following link to access all reference material.

<https://keysenergy0.sharepoint.com/:f:/s/Purchasing/ErF8yMdjUxhEmzbYhRVjZDgBeWTwafN1vVNVpuL1X4LYw?e=PXd0cP>